

NE Kennedy Drive Water Main Replacement Water CIP Project #R3

Project Partners

Design Engineer: PACE

Contractor: Strickland & Sons Excavation

Contract Amount

The Contractor was awarded the project's Base Bid along with BOTH alternate bid schedules for a total of **\$474,220.92** (tax included).

Schedule Overview

June	Mobilization, begin excavation and installation
July	Complete installation and testing, possible overlay
August	Complete remaining project items

Project Description

The proposed project consists of replacing approximately 1,150 linear feet of 4-inch and 6-inch Asbestos Concrete and PVC water main with 8-inch Ductile Iron water main in NE Kennedy Drive. The project will include replacing an existing fire hydrant, 13 water services, and other system appurtenances along with connections to the existing water system.

The project will include associated asphalt grinding and roadway overlay along with other surface restoration. The contract includes 60 working days for completion.

Questions? Contact:

Shaun Tozer Project Manager

Phone: 425-939-8046 or at

Email: shaun.tozer@duvallwa.gov



Small Town. Real Life.

Check www.duvallwa.gov or follow the City of Duvall on Facebook and Twitter for up to date information about this project's progress.